

# BANKABILITY STUDY Esdec FlatFix Wave Series

**Esdec Solar Group** 

Document No. : 22-0801 Issue: 1 Status : Final Date: 2022-09-15





Project name:	Bankability Study
Report title:	Esdec FlatFix Wave Series
Customer:	Esdec Solar Group, Londenstraat 16,
	7418 EE Deventer, The Netherlands
Contact person:	Arno Damhuis
Date of issue:	2022-09-15
Project No.:	10344323
Document No.:	22-0801
Issue/Status:	Issue 1/ Final

**Energy Systems** 

DNV Netherlands B.V. Utrechtseweg 310-B50 6812 AR Arnhem The Netherlands

Tel: +31 26 356 9111 Registered Arnhem 09006404

Task and objective:

This report presents the results of bankability study of the Esdec FlatFix Wave Series.

Prepared by: Verified by: Approved by: S. Sriram P. Raats R. van Dijk Co-authors: L. Sanso M. Reza

Strictly Confidential	For disclosure only to named individuals within the Customer's organization.	Keywords: Mounting Structure, Solar,
Private and Confidential	For disclosure only to individuals directly concerned with the subject matter of the document within the Customer's organization.	Technology review
□ Commercial in Confidence	Not to be disclosed outside the Customer's organization.	
DNV only	Not to be disclosed to non-DNV staff	
⊠ Customer's Discretion	Distribution for information only at the discretion of the Customer (subject to the above Important Notice and Disclaimer and the terms of DNV's written agreement with the Customer).	
□ Published	Available for information only to the general public (subject to the above Important Notice and Disclaimer).	

Copyright © DNV 2022. All rights reserved. Unless otherwise agreed in writing: (i) This publication or parts thereof may not be copied, reproduced or transmitted in any form, or by any means, whether digitally or otherwise; (ii) The content of this publication shall be kept confidential by the customer; (iii) No third party may rely on its contents; and (iv) DNV undertakes no duty of care toward any third party. Reference to part of this publication which may lead to misinterpretation is prohibited

Issue	Date	Reason for Issue	Prepared by	Verified by	Approved by
1	2022-09-15	Final Report	S. Sriram ; L. Sanso ; M. Reza,	P. Raats	R. van Dijk



# **Table of Contents**

1         INTRODUCTION         1           1.1 Scope of Work         1           1.2 Methodology         1           1.3 Assumptions         1           1.3 Assumptions         1           2         PRODUCT EVALUATION         2           2.1 System Description         2           2.1.1         System Components         2           2.1.2         Mounting System Assembly         4           2.2 Design Parameters         6           2.2.1         Array Layout Rules         6           2.2.2         Design key items         6           2.3.3         Load Combinations         6           2.3.4         Strength         8           2.3.5         Corrosion         9           2.4.1         Functional grounding, bonding and lightning protection         9           2.4.2         Wire Management         10           3         RELIABILITY / DURABILITY EVALUATION         11           4         MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION         12           4.1 Introduction         12         13           4.3 Strength         13         13           4.3 Stupply Management         14         14 <t< th=""><th>EXECUTIVE SUMMARY</th><th> VI</th></t<>	EXECUTIVE SUMMARY	VI
1.2 Methodology       1         1.3 Assumptions       1         2 PRODUCT EVALUATION       2         2.1 System Components       2         2.1.1 System Components       2         2.1.2 Mounting System Assembly       4         2.2 Design Parameters       6         2.2.1 Array Layour Rules       6         2.2.2 Design key items       6         2.3 Structural Engineering       6         2.3.1 Wind Load       7         2.3.2 Snow Load       8         2.3.3 Load Combinations       8         2.3.4 Strength       8         2.3.5 Corrosion       9         2.4.1 Functional grounding, bonding and lightning protection       9         2.4.2 Wire Management       10         3 RELIABILITY / DURABILITY EVALUATION       11         3.1 Test Programs and Certificates       11         3.1 Structural Engineering       12         4.1 Introduction       12         4.2 Site Visit       13         4.3 Supply Management       10         4.4 Manufacturing Procedure       14         4.5 Installation       14         4.4 Manufacturing Procedure       14         4.5 Installation       15      <	1 INTRODUCTION	1
1.3 Assumptions       1         2 PRODUCT EVALUATION       2         2.1 System Description       2         2.1.1 System Components       2         2.1.2 Mounting System Assembly       4         2.2 Design Parameters       6         2.2.1 Array Layout Rules       6         2.2.2 Design Perameters       6         2.3.1 Array Layout Rules       6         2.3.2 Design key items       6         2.3.1 Wind Load       7         2.3.2 Snow Load       7         2.3.3 Load Combinations       8         2.3.4 Strength       8         2.3.5 Corrosion       9         2.4.1 Functional grounding, bonding and lightning protection       9         2.4.2 Wire Management       10         3 RELIABILITY / DURABILITY EVALUATION       11         3.1 Test Programs and Certificates       11         4.1 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION       12         4.3 Supply Management       13         4.4 Manufacturing Procedure       14         4.5 Installaltion       14         4.6 Maintenance and Inspection       15         5 BUSINESS EVALUATION       15         5 BUSINESS EVALUATION       15	1.1 Scope of Work	1
1.3 Assumptions       1         2 PRODUCT EVALUATION       2         2.1 System Description       2         2.1.1 System Components       2         2.1.2 Mounting System Assembly       4         2.2 Design Parameters       6         2.2.1 Array Layout Rules       6         2.2.2 Design key items       6         2.3.1 Wind Load       7         2.3.2 Snow Load       7         2.3.3 Load Combinations       8         2.3.4 Strength       8         2.3.5 Corrosion       9         2.4.1 Functional grounding, bonding and lightning protection       9         2.4.2 Wire Management       10         3 RELIABILITY / DURABILITY EVALUATION       11         3.1 Test Programs and Certificates       11         4.1 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION       12         4.1 Manufacturing Procedure       13         4.3 Supply Management       13         4.4 Manufacturing Procedure       14         4.5 Installaltion       14         4.6 Maintenance and Inspection       15         5 BUSINESS EVALUATION       15         5 I Financial Overview       17         5.1 Financial Overview       17	1.2 Methodology	1
2.1 System Description       2         2.1.1       System Components       2         2.1.2       Mounting System Assembly       4         2.2 Design Parameters       6         2.2.1       Array Layout Rules       6         2.2.2       Design key items       6         2.3 Structural Engineering       6         2.3.1       Wind Load       7         3.2       Snow Load       8         2.3.3       Load Combinations       8         2.3.4       Strength       8         2.3.5       Corrosion       9         2.4.1       Functional grounding, bonding and lightning protection       9         2.4.2       Wire Management       10         3       RELIABILITY / DURABILITY EVALUATION       11         3.1       Test Programs and Certificates       11         1.1       1.1       1.1         3.1       Test Programs and Certificates       12         4.1       Introduction       12         4.2       Site Visit       13         4.3       Supply Management       14         4.6       Manufacturing Procedure       14         4.7       Spare Parts       15		
2.1 System Description       2         2.1.1       System Components       2         2.1.2       Mounting System Assembly       4         2.2 Design Parameters       6         2.2.1       Array Layout Rules       6         2.2.2       Design key items       6         2.3 Structural Engineering       6         2.3.1       Wind Load       7         3.2       Snow Load       8         2.3.3       Load Combinations       8         2.3.4       Strength       8         2.3.5       Corrosion       9         2.4.1       Functional grounding, bonding and lightning protection       9         2.4.2       Wire Management       10         3       RELIABILITY / DURABILITY EVALUATION       11         3.1       Test Programs and Certificates       11         1.1       1.1       1.1         3.1       Test Programs and Certificates       12         4.1       Introduction       12         4.2       Site Visit       13         4.3       Supply Management       14         4.6       Manufacturing Procedure       14         4.7       Spare Parts       15		0
21.1       System Components       2         2.1.2       Mounting System Assembly       4         2.2 Design Parameters.       6         2.2.1       Array Layout Rules       6         2.2.2       Design key items       6         2.3 Structural Engineering       6         2.3.1       Wind Load       7         2.3.2       Snow Load       8         2.3.3       Load Combinations       8         2.3.4       Strength       8         2.3.5       Corrosion       9         2.4.1       Functional grounding, bonding and lightning protection       9         2.4.2       Wire Management       10         3       RELIABILITY / DURABILITY EVALUATION       11         3.1       Test Programs and Certificates       11         4       MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION       12         4.2       Steit Visit       13         4.3       Supply Management       13         4.4       MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION       12         4.2       Steit Visit       13         4.3       Supply Management       13         4.4       Steit Visit       13		
2.1.2     Mounting System Assembly     4       2.2 Design Parameters     6       2.2.1     Array Layout Rules     6       2.2.2     Design key items     6       2.3.1     Wind Load     7       2.3.2     Snow Load     7       2.3.3     Load Combinations     8       2.3.4     Strength     8       2.3.5     Corrosion     9       2.4.1     Functional grounding, bonding and lightning protection     9       2.4.2     Wire Management     10       3     RELIABILITY / DURABILITY EVALUATION     11       3.1     Test Programs and Certificates     11       4     MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION     12       4.1     Introduction     12       4.2     Steply Management     13       4.3     Assupply Management     13       4.4     Assupply Management     14       4.6     Maintenance and Inspection     14       4.7     Spare Parts     15       5     BUSINESS EVALUATION     15       5     SUSINESS EVALUATION     15       5     JI Financial Overview     17       5.3     Isinatilation     14       4.5     Steplate and Usion     15		2
2.2 Design Parameters.       6         2.2.1       Array Layout Rules       6         2.2.2       Design key items       6         2.3 Structural Engineering       6         2.3.1       Wind Load       7         2.3.2       Snow Load       8         2.3.3       Load Combinations       8         2.3.4       Strength       8         2.3.5       Corrosion       9         2.4.1       Functional grounding, bonding and lightning protection       9         2.4.1       Functional grounding, bonding and lightning protection       9         2.4.2       Wire Management       10         3       RELIABILITY / DURABILITY EVALUATION       11         3.1 Test Programs and Certificates       11         14       MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION       12         4.1 Introduction       12         4.2 Site Visit       13         4.3 Supply Management       13         4.4 Manufacturing Procedure       14         4.5 Installation       14         4.6 Maintenance and Inspection       14         4.7 Spare Parts       15         5.1 Financial Overview       15         5.1 Financial Ov		4
2.2.1Array Layout Rules62.2.2Design key items62.3 Structural Engineering62.3.1Wind Load72.3.2Snow Load82.3.3Load Combinations82.3.4Strength82.3.5Corrosion92.4.1Functional grounding, bonding and lightning protection92.4.2Wire Management103RELIABILITY / DURABILITY EVALUATION113.1Test Programs and Certificates114MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION124.1Introduction124.2Site Visit134.3 Supply Management134.4 Manufacturing Procedure144.6 Maintenance and Inspection144.7 Spare Parts155BUSINESS EVALUATION155BUSINESS EVALUATION155JUSINESS EVALUATION195.3 Intellectual Property20		
2.2.2       Design key items       6         2.3 Structural Engineering       6         2.3.1       Wind Load       7         2.3.2       Snow Load       8         2.3.3       Load Combinations       8         2.3.4       Strength       8         2.3.5       Corrosion       9         2.4.1       Functional grounding, bonding and lightning protection       9         2.4.2       Wire Management       10         3       RELIABILITY / DURABILITY EVALUATION       11         3.1       Test Programs and Certificates       11         4.1       Introduction       12         4.2       Site Visit       13         4.3       Supply Management       12         4.4       Manufacturing Procedure       14         4.5       Installation       14         4.6       Maintenance and Inspection       14         4.7       Spare Parts       15         5       BUSINESS EVALUATION       15         5.1       Financial Overview       17         5.2       Product Roadmap and Vision       19         3.3       Intellectual Property       20		
2.3 Structural Engineering62.3.1Wind Load72.3.2Snow Load82.3.3Load Combinations2.3.4Strength882.3.5Corrosion92.4 Electrical Engineering92.4.1Functional grounding, bonding and lightning protection92.4.2Wire Management103RELIABILITY / DURABILITY EVALUATION113.1 Test Programs and Certificates114MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION124.1 Introduction124.2 Site Visit134.3 Supply Management144.6 Maintenance and Inspection1558 USINESS EVALUATION1558 USINESS EVALUATION155.1 Financial Overview175.2 Product Roadmap and Vision193.3 Intellectual Property		6
2.3.1       Wind Load       7         2.3.2       Snow Load       8         2.3.3       Load Combinations       8         2.3.4       Strength       8         2.3.5       Corrosion       9         2.4.1       Functional grounding, bonding and lightning protection       9         2.4.1       Functional grounding, bonding and lightning protection       9         2.4.2       Wire Management       10         3       RELIABILITY / DURABILITY EVALUATION       11         3.1 Test Programs and Certificates       11         4       MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION       12         4.1 Introduction       12         4.2 Site Visit       13         4.3 Supply Management       13         4.4 Manufacturing Procedure       14         4.5 Installation       14         4.6 Maintenance and Inspection       14         4.7 Spare Parts       15         5       BUSINESS EVALUATION       15         5.1 Financial Overview       17         5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20	- · ·	6
2.3.3Load Combinations82.3.4Strength82.3.5Corrosion92.4 Electrical Engineering.92.4.1Functional grounding, bonding and lightning protection92.4.2Wire Management103RELIABILITY / DURABILITY EVALUATION113.1 Test Programs and Certificates114MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION124.1 Introduction124.2 Site Visit134.3 Supply Management134.4 Manufacturing Procedure144.5 Installation144.6 Maintenance and Inspection144.7 Spare Parts155BUSINESS EVALUATION155BUSINESS EVALUATION155SUSINESS EVALUATION15		
2.3.4Strength82.3.5Corrosion92.4.4Functional grounding, bonding and lightning protection92.4.2Wire Management103RELIABILITY / DURABILITY EVALUATION113.1 Test Programs and Certificates114MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION124.1 Introduction124.2 Site Visit134.3 Supply Management134.4 Manufacturing Procedure144.5 Installation144.6 Maintenance and Inspection155BUSINESS EVALUATION155BUSINESS EVALUATION155.1 Financial Overview175.3 Intellectual Property20		
2.3.5Corrosion92.4 Electrical Engineering.92.4.1Functional grounding, bonding and lightning protection92.4.2Wire Management103RELIABILITY / DURABILITY EVALUATION113.1 Test Programs and Certificates114MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION124.1 Introduction124.2 Site Visit134.3 Supply Management134.4 Manufacturing Procedure144.5 Installation144.6 Maintenance and Inspection155BUSINESS EVALUATION155BUSINESS EVALUATION155.1 Financial Overview175.3 Intellectual Property.20		
2.4 Electrical Engineering.       9         2.4.1       Functional grounding, bonding and lightning protection       9         2.4.2       Wire Management       10         3       RELIABILITY / DURABILITY EVALUATION       11         3.1       Test Programs and Certificates       11         4       MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION       12         4.1       Introduction       12         4.2       Site Visit       13         4.3       Supply Management       13         4.4       Manufacturing Procedure       14         4.5       Installation       14         4.6       Maintenance and Inspection       14         4.7       Spare Parts       15         5       BUSINESS EVALUATION       15         5.1       Financial Overview       17         5.2       Product Roadmap and Vision       19         5.3       Intellectual Property.       20		
2.4.1Functional grounding, bonding and lightning protection92.4.2Wire Management103RELIABILITY / DURABILITY EVALUATION113.1 Test Programs and Certificates114MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION124.1 Introduction124.2 Site Visit134.3 Supply Management134.4 Manufacturing Procedure144.5 Installation144.6 Maintenance and Inspection144.7 Spare Parts155BUSINESS EVALUATION155.1 Financial Overview175.3 Intellectual Property20		-
2.4.2Wire Management103RELIABILITY / DURABILITY EVALUATION113.1Test Programs and Certificates114MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION124.1Introduction124.2Site Visit134.3Supply Management134.4Manufacturing Procedure144.5Installation144.6Maintenance and Inspection155BUSINESS EVALUATION155BUSINESS EVALUATION155.1Financial Overview175.2Product Roadmap and Vision195.3Intellectual Property20		
3       RELIABILITY / DURABILITY EVALUATION       11         3.1       Test Programs and Certificates       11         4       MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION       12         4.1       Introduction       12         4.1       Introduction       12         4.2       Site Visit       13         4.3       Supply Management       13         4.4       Manufacturing Procedure       14         4.5       Installation       14         4.6       Maintenance and Inspection       14         4.7       Spare Parts       15         4.8       Warranty       15         5       BUSINESS EVALUATION.       15         5.1       Financial Overview       17         5.2       Product Roadmap and Vision       19         5.3       Intellectual Property.       20		-
3.1 Test Programs and Certificates       11         4       MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION       12         4.1 Introduction       12         4.2 Site Visit       13         4.3 Supply Management       13         4.4 Manufacturing Procedure       14         4.5 Installation       14         4.6 Maintenance and Inspection       14         4.7 Spare Parts       15         5       BUSINESS EVALUATION       15         5.1 Financial Overview       17         5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20		
4       MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.       12         4.1       Introduction.       12         4.2 Site Visit       13         4.3 Supply Management.       13         4.4 Manufacturing Procedure       14         4.5 Installation       14         4.6 Maintenance and Inspection       14         4.7 Spare Parts       15         4.8 Warranty       15         5       BUSINESS EVALUATION       15         5.1 Financial Overview       17         5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20		
4       MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.       12         4.1       Introduction.       12         4.2 Site Visit       13         4.3 Supply Management.       13         4.4 Manufacturing Procedure       14         4.5 Installation       14         4.6 Maintenance and Inspection       14         4.7 Spare Parts       15         4.8 Warranty       15         5       BUSINESS EVALUATION       15         5.1 Financial Overview       17         5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20	3 RELIABILITY / DURABILITY EVALUATION	11
4.1 Introduction124.2 Site Visit134.3 Supply Management134.4 Manufacturing Procedure144.5 Installation144.6 Maintenance and Inspection144.7 Spare Parts154.8 Warranty155 BUSINESS EVALUATION155.1 Financial Overview175.2 Product Roadmap and Vision195.3 Intellectual Property20		
4.2 Site Visit134.3 Supply Management134.4 Manufacturing Procedure144.5 Installation144.6 Maintenance and Inspection144.7 Spare Parts154.8 Warranty155 BUSINESS EVALUATION155.1 Financial Overview175.2 Product Roadmap and Vision195.3 Intellectual Property20	3.1 Test Programs and Certificates	11
4.3 Supply Management.134.4 Manufacturing Procedure144.5 Installation144.6 Maintenance and Inspection.144.7 Spare Parts154.8 Warranty155 BUSINESS EVALUATION.155.1 Financial Overview175.2 Product Roadmap and Vision195.3 Intellectual Property20	3.1 Test Programs and Certificates	11
4.4 Manufacturing Procedure144.5 Installation144.6 Maintenance and Inspection144.7 Spare Parts154.8 Warranty155 BUSINESS EVALUATION155.1 Financial Overview175.2 Product Roadmap and Vision195.3 Intellectual Property20	<ul> <li>3.1 Test Programs and Certificates</li></ul>	11
4.4 Manufacturing Procedure144.5 Installation144.6 Maintenance and Inspection144.7 Spare Parts154.8 Warranty155 BUSINESS EVALUATION155.1 Financial Overview175.2 Product Roadmap and Vision195.3 Intellectual Property20	<ul> <li>3.1 Test Programs and Certificates</li></ul>	11 12 12
4.5 Installation       14         4.6 Maintenance and Inspection       14         4.7 Spare Parts       15         4.8 Warranty       15         5 BUSINESS EVALUATION       15         5.1 Financial Overview       17         5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20	<ul> <li>3.1 Test Programs and Certificates</li> <li>4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li> </ul>	11 
4.6 Maintenance and Inspection144.7 Spare Parts154.8 Warranty155 BUSINESS EVALUATION155.1 Financial Overview175.2 Product Roadmap and Vision195.3 Intellectual Property20	<ul> <li>3.1 Test Programs and Certificates</li> <li>4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li></ul>	
4.7 Spare Parts       15         4.8 Warranty       15         5 BUSINESS EVALUATION       15         5.1 Financial Overview       17         5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20	<ul> <li>3.1 Test Programs and Certificates</li> <li>4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure</li> </ul>	
4.8 Warranty       15         5 BUSINESS EVALUATION       15         5.1 Financial Overview       17         5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20	<ul> <li>3.1 Test Programs and Certificates</li> <li>4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure</li> <li>4.5 Installation</li> </ul>	
5 BUSINESS EVALUATION	<ul> <li>3.1 Test Programs and Certificates</li> <li>4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li></ul>	
5.1 Financial Overview       17         5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20	<ul> <li>3.1 Test Programs and Certificates</li> <li>MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit .</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure .</li> <li>4.5 Installation .</li> <li>4.6 Maintenance and Inspection.</li> <li>4.7 Spare Parts .</li> </ul>	
5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20	<ul> <li>3.1 Test Programs and Certificates</li> <li>MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit .</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure .</li> <li>4.5 Installation .</li> <li>4.6 Maintenance and Inspection.</li> <li>4.7 Spare Parts .</li> </ul>	
5.2 Product Roadmap and Vision       19         5.3 Intellectual Property       20	<ul> <li>3.1 Test Programs and Certificates</li> <li>4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure</li> <li>4.5 Installation</li> <li>4.6 Maintenance and Inspection.</li> <li>4.7 Spare Parts</li> <li>4.8 Warranty</li> </ul>	
5.3 Intellectual Property	<ul> <li>3.1 Test Programs and Certificates</li> <li>4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure</li> <li>4.5 Installation</li> <li>4.6 Maintenance and Inspection.</li> <li>4.7 Spare Parts</li> <li>4.8 Warranty.</li> <li>5 BUSINESS EVALUATION.</li> </ul>	
	<ul> <li>3.1 Test Programs and Certificates</li> <li>4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure</li> <li>4.5 Installation</li> <li>4.6 Maintenance and Inspection.</li> <li>4.7 Spare Parts</li> <li>4.8 Warranty.</li> <li>5 BUSINESS EVALUATION.</li> <li>5.1 Financial Overview</li> </ul>	
6 CONCLUDING REMARKS	<ul> <li>3.1 Test Programs and Certificates</li> <li>4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure</li> <li>4.5 Installation</li> <li>4.6 Maintenance and Inspection.</li> <li>4.7 Spare Parts</li> <li>4.8 Warranty</li> <li>5 BUSINESS EVALUATION.</li> <li>5.1 Financial Overview</li> <li>5.2 Product Roadmap and Vision.</li> </ul>	
	<ul> <li>3.1 Test Programs and Certificates</li> <li>MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure</li> <li>4.5 Installation</li> <li>4.6 Maintenance and Inspection.</li> <li>4.7 Spare Parts</li> <li>4.8 Warranty.</li> <li>5 BUSINESS EVALUATION.</li> <li>5.1 Financial Overview</li> <li>5.2 Product Roadmap and Vision.</li> <li>5.3 Intellectual Property.</li> </ul>	
7 REFERENCES	<ul> <li>3.1 Test Programs and Certificates</li> <li>MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION.</li> <li>4.1 Introduction.</li> <li>4.2 Site Visit</li> <li>4.3 Supply Management.</li> <li>4.4 Manufacturing Procedure</li> <li>4.5 Installation</li> <li>4.6 Maintenance and Inspection.</li> <li>4.7 Spare Parts</li> <li>4.8 Warranty.</li> <li>5 BUSINESS EVALUATION.</li> <li>5.1 Financial Overview</li> <li>5.2 Product Roadmap and Vision.</li> <li>5.3 Intellectual Property.</li> </ul>	



# List of figures

Figure 2-1 FlatFix Wave system	2
Figure 2-2 FlatFix Wave system – Components. Source: System datasheet	
Figure 2-3 FlatFix Wave system – FlatFix Wave exploaded view. Source: System assembly manual	5
Figure 2-4 FlatFix Wave array/segment in the scale wind tunnel by Peutz (left) and uplift test by Esdec (right)	7
Figure 2-5 FlatFix Wave MLT bending test	
Figure 2-6 FlatFix Wave Teeth surfaces	
Figure 4-1 the access and safety marks on site	13
Figure 4-2 FlatFix Wave walkway spacing	15
Figure 5-1 Esdec Business Units	16
Figure 5-2 Esdec history and growth over the years	17
Figure 5-3 Research & Development Vision	19

# List of tables

Table 2-1 FlatFix Wave design guidelines	6
Table 3-1 FlatFix Wave Product Test Certificates	
Table : Summary of key financial figures( x1000 EUR)	18



## List of abbreviations

Abbrevia- tion	Meaning
AHJ	Authority Having Jurisdiction
DNV	Det Norske Veritas
EBITDA	Earnings before interest, taxes, depreciation, and amortization
EN	European Standard (e.g. Eurocode)
ETN	Enquête de Technique Nouvelle
GCR	Ground Coverage Ratio
GM	Ground-mount
Н	Building Height
IBC	International Building Code
IE	Independent Engineer
L	Left
MA	Mechanical Attachment
MC4	Multi-Contact, 4 millimetre (connector/cable)
MLT	Mechanical Load Test
PV	PhotoVoltaics
R	Right
VDE	Verband der Elektrotechnik, Elektronik und Informationstechnik
ZM	Zinc-Aluminum-Magnesium



#### **EXECUTIVE SUMMARY**

DNV has been engaged by Esdec Solar Group (Customer/Esdec) to undertake an independent technology assessment of a solar rooftop mounting system called Esdec FlatFix Wave. The aim of the assessment is to provide an independent opinion on the system that can be used by Esdec to increase the reliability in stakeholders decisions.

DNV started the review in April 2022 and finished in August 2022.

#### **Business Evaluation**

Esdec is founded in 2004 and is now part of the Esdec Solar Group. The Esdec Solar Group was founded in 2018 and consists of 7 business-units operating worldwide. These business units share R&D knowhow, market regulations and particularities, test facilities / knowhow and support services.Turnover is nowadays up to half a billion euros and the Group has over 400 employees. Futher information is given in chapter 5.

### **Product Evaluation**

DNV has assessed the following information as part of the system overview;

- Design documentation including experimental tests
- Design documentation of the Esdec design software
- Production installation and maintenance manuals

Esdec's FlatFix Wave system is a fixed-tilt, rooftop PV racking system consisting of steel structural members, wind deflectors, and specially-designed mounting connectors to support the PV modules. Esdec rooftop systems are ballasted systems designed for both commercial and industrial flat roofs. The FlatFix Wave system is arranged as a dual tilt system with -10° and 10° tilt angles, with modules facing east and west.

DNV has conducted a review and conformity analysis of the relevant system assembly, electrical and structural aspects, wind tunnel reports, certificates, component and system strength testing, and component and project layout. Esdec's understanding and investment in the wind tunnel testing program are industry-leading. Esdec's standard structural calculations package, combining wind tunnel and mechanical lift test data supplemented with (national) Eurocode regulations, is acceptable for Authorities Having Jurisdiction (AHJ) such as France, Netherlands, Germany and, generally, EU countries. Finally, Esdec's structural testing program is extensive and DNV looks very favorably on the rigor, quality, and documentation of performed tests.

### **Reliability Evaluation**

DNV reviewed all available tests and certificates regarding the structural integrity and the resistance against environmental conditions and accidents. The tests cover comprehensive topics including fire resistance, corrosion, earthing, lightning and wind tunnel load measurement. DNV observed that all tests of the functionality of the system have been performed according international standards

#### **Manufacturing Quality Evaluation**

Esdec acquired ISO 9001-2015 (May, 2022), the certified for its Quality Management System that aims creating the highest possible customer satisfaction certificate, with no non-conformity issue. The outcome of the ISO audit showed that the sales and marketing processes have high quality and clear strategy. Currently, Esdec focuses on plans to improve the logistics and delivery of the product. DNV visited Esdec headquarter and main storage and logistic space, administration and design



offices and the mechanical and electrical workshops. Based on the observations and certificates, DNV expects the same quality for the manufacturing processes considering Esdec is regularly audited for Factory Production Control, however, DNV has not visited the manufacturing facilities.

#### **Operations and Maintenance**

Esdec provided documentation and recommendation regarding the installation, operation and the maintenance of the product. Customer also have detailed sales terms and conditions and warranty agreement. DNV assessed the installation manual as part of the product evaluation. Additionally, DNV has observed that Esdec holds inspection and maintenance forms and they use international recommended practices as the base for their inspection and maintenance recommendations.

#### **Concluding Remarks**

In its role as independent engineer, in addition to information gathered from Esdec representative, DNV has studied documentation provided by Esdec regarding the technical aspects of the FlatFix Wave mounting system, along with manufacturing and business systems. Based on available information, testing and engineering that is indicated to have gone into the FlatFix Wave rooftop mounting products, DNV considers Esdec to be an organization which is well funded with strong financial health that, through qualitative design processes and extensive test procedures, is capable to supply suitable mounting systems that do not pose any atypical risks.



#### **1 INTRODUCTION**

Esdec Solar B.V. (Esdec) requested DNV Netherlands B.V. (DNV) to conduct a Bankability Study of the FlatFix Wave Series of solar flat roof mounting system.

The study focuses on the FlatFix Wave (10° tilt) mounting system. The FlatFix Wave mounting system is a ballasted system designed for commercial and industrial roof applications.

#### 1.1 Scope of Work

The primary objective of this report is to assess factors that would affect the final product's performance and reliability in the field and the Company's ability to deliver and service the products. Such factors include the product design, quality of materials, product performance, regulatory compliance, reliability tests, and the manufacturing and quality control processes.

DNV has divided the bankability study into several main topics for evaluation as following :

- Product Evaluation
- Reliability/Durability Evaluation
- Manufacturing and Quality Evaluation
- Operation and Maintenance Evaluation
- Business Evaluation

To perform the assessment, DNV relied on documentation provided by Esdec and conversations with key staff associated with the topic areas covered.

#### 1.2 Methodology

Studies of this type are often conducted to provide potential investors and financial institutions with an increased level of confidence that the product can perform according to the manufacturer's stated claims and industry expectations. This report will be directed to an audience of Esdec clients, PV project developers, and financiers.DNV is uniquely qualified to conduct this study due to its extensive background and experience in solar independent engineering and technology due diligence work.

This report is based upon information provided by Esdec to DNV via electronic media, direct meeting and phone calls. The information provided to DNV for review has included engineering drawings, test reports, installation procedures, quality plans, operations and maintenance documentation, and numerous related documents. DNV has not visited Esdec's manufacturing facilities but reviewed documentation to understand and evaluate the manufacturing approach.

Esdec has been open and forthcoming in providing the data requested. The primary Esdec contributor of information for this report was Arno Damhuis, Manager Compliance & Testing at Esdec Solar Group.

#### 1.3 Assumptions

This report summarizes DNV's assessment of the technology and relies on the accuracy of the information provided by Esdec. Esdec has been open and forthcoming in providing the data that DNV has requested.

This report is based on some information not within the control of DNV. DNV believes that the information provided by others is true and correct and reasonable for the purposes of this report. DNV has not been requested to make an independent analysis or verification of the validity of such information. DNV does not guarantee the accuracy of the data, information, or opinions provided by others.



In preparing this report and the opinions presented herein, DNV has made certain assumptions with respect to conditions that may exist, or events that may occur in the future. DNV believes that these assumptions are reasonable for the purposes of this report, but actual events or conditions may cause results to differ materially from forward-looking statements.

## 2 PRODUCT EVALUATION

The technology evaluation focuses on the FlatFix Wave (10° tilt) mounting system structural and electrical conformities.

### 2.1 System Description

The FlatFix Wave mounting system is a ballasted system designed for commercial and industrial roof applications. The FlatFix Wave system concept and its appearance on a rooftop are shown in Figure 2-1.



Figure 2-1 FlatFix Wave system

#### 2.1.1 System Components

The FlatFix Wave system is composed of six major components: FlatFix Wave Dual Unit, FlatFix Wave Connection pin, FlatFix Wave Cable and Ballast brackets, FlatFix Wave Wind deflector Set L&R, FlatFix Wave Stabilizer and FlatFix Wave Base plate (Figure 2-2). See an exploaded view in Figure 2-3.

All structural components are S250GD steel class and Magnelis coated. The exceptions are FlatFix Wave brackets and FlatFix Wave Connector pin made of steel Bezinal-protected and FlatFix Wave Base plate of Mafill (high-quality polypropylene). All deemed as suitable for their structural purpose according to DNV's viewpoint.

FlatFix Wave Dual Unit is a highly engineered component that gets shipped to the project site with preinstalled roof supports called Base plate. FlatFix Wave Dual Unit is the key element of the system.

FlatFix Wave Dual Unit comes in three configurations: FlatFix Wave Dual Start Unit, FlatFix Wave Dual Unit and FlatFix Wave Dual Unit 2P, and they accommodate two different module widths: 990 mm to 1,070 mm (DR1) and 1,070 mm to 1,150 mm (DR2). With regards to module dimensions, FlatFix Wave is suitable for: i) Up to 2,400x1,150 mm; and ii) from 2,400 up to 2,500x1,150 mm with extra measurements for edge zones. It praises the versatility of the system.

Below, FlatFix Wave Dual Unit is shown together with the rest of structural components.






Figure 2-2 FlatFix Wave system – Components. Source: System datasheet



### 2.1.2 Mounting System Assembly

FlatFix Wave system is shipped to the site and arrives with several accessories preassembled, but the part of the mechanical assembly is completed on the roof, based on the layout drawing and installation manual provided by Esdec.

FlatFix Wave system is a unique toolless solution to install, easy to understand and unfold. All these properties allow for a significant labor time saving and make the system cost effective. The uniqueness of its mechanism makes it significantly unconventional in comparison with other systems but DNV does not expect assembly or operating issues. Specially, since this mechanism plays an important role during installation and can be controlled during manufacturing quality control (see section 4).

Below, main assembly phases are summarized by two pictures. Firstly, the unfolding process of the FlatFix Wave Dual Unit is shown. It comprises the unfolding of the High bases as well.

Secondly, the rest of the components are added to the system in an easy manner. They are fixed by predefined clamps, lips and perforations to FlatFix Wave Dual Units, High bases and Stabilizers.

In particular, DNV highlights that MC4 connections and cables as well as ballast pieces are proposed to be installed in a controlled and predefined manner.

#### **3 PLACE DUAL START UNIT**





Figure 2- 3 FlatFix Wave system – FlatFix Wave Dual Unit unfolding. Source: System assembly manual



#### **1 BILL OF MATERIALS**



#### UNITS



1a. FlatFix Wave Dual Start unit 4P DR1 1009101 1b. FlatFix Wave Dual Start unit 4P DR2 1009151

2a. FlatFix Wave Dual Unit 4P DR1

2b. FlatFix Wave Dual Unit 4P DR2

3a. FlatFix Wave Dual Unit 2P DR1

3b. FlatFix Wave Dual Unit 2P DR2

1009100

1009150


1009102

1009152



DR1 (Dual range 1): panel widths 990mm to 1070mm DR2 (Dual range 2): panel widths 1070mm to 1150mm

# WIND DEFLECTORS



6. FlatFix Wave Winddeflector DR1 kit ( = wind deflector L and R) 1009103 7. FlatFix Wave Connector pin (set of 3) 1009122

8. FlatFix Wave Roof support 1009120

#### STABILIZERS



4a. FlatFix Wave Stabilizer 2900 1009110 4b. FlatFix Wave Stabilizer 3530 1009111 4c. FlatFix Wave Stabilizer 4000 1009114 4d. FlatFix Wave Stabilizer 4350 1009115

5. FlatFix Wave Cable bracket 1009124

#### ACCESSORIES



8. FlatFix Wave Roof support 1009120



9. FlatFix Wave Ballast bracket 1009123

Figure 2-3 FlatFix Wave system – FlatFix Wave exploaded view. Source: System assembly manual



### 2.2 Design Parameters

The project engineering process is provided by Esdec. For that purpose, Esdec has set up an online calculator (<u>https://eu.Esdec.com/en/calculator/#</u>) that is an easy step for any interested person or party. It evaluates all design loads based on the provided site criteria and then apply a comprehensive design guidelines ruleset before generating a Project Plan for use in permitting, budgeting, and system construction. In case of insufficient input or critical or complex design situations, Esdec's project engineers will be consulted for calculations, advice, etc.

#### 2.2.1 Array Layout Rules

Typical flat-roof arrays sizes are governed by roof conditions, electrical requirements and thermal effects. Esdec restricts array sizes to 40 m x 40 m (for flat roofs) and distance to edge of the roof to around 1/5 times the building height to avoid the very turbulent winds at this area.

DNV highlights that Esdec complies with the IBC fire code. According to it, array sizes cannot exceed 45 m x 45 m (see below "Fire listing" in chapter 3.1.

### 2.2.2 Design key items

DNV has summarized key technical information pertinent to the FlatFix Wave design guidelines in Table 2-1.

Parameter	Description	Meets IE expectations?
Roof Loading	≈14 kg/m² to ≈22 kg/m² including racking, modules, and ballast.	Yes, see note 1)
Roof Slope	5° max slope (1/12 pitch) in all directions.	Yes, see note 2)
Wavy Roofs	One segment is not designed to go over roof cricketing.	Yes
Wind Speed	Wind speeds require Esdec engineering review.	Yes, see Section 2.3.1
Exposures	According to Eurocode – National Annexes	Yes
Maximum Building Height	Maximum Building Height requires Esdec engineering review. Specially, if exceeding 12.0 m high.	Yes

Table 2-1 FlatFix Wave design guidelines

#### Notes:

- 1) FlatFix Wave roof loading range allows system owners to deploy solar PV systems on roofs with low additional roof capacity available.
- According to Peutz's letter, the wind tunnel data are valid for roof tilt angles between -5° and +5°. Values outside these bounds will require to contact Esdec.

## 2.3 Structural Engineering

As with any PV mounting systems, main physical loads applied to the Esdec's FlatFix Wave structure originate from wind loads, dead loads (racking system and ballast self-weights and PV modules) and snow loads. Standard requirements for the applied loads are considered according to *Eurocode EN 1991* for European countries.



The primary structural requirement for the racking structure is to support the PV modules without significant deformation or strength failures under the aforementioned design forces for the design life of the generating facility.

#### 2.3.1 Wind Load

Generally, Esdec informs that maximum wind speed resisted by FlatFix Wave system is Beaufort Scale 11 (103 km/h to 116 km/h). If any of the prescribed wind limits is exceeded by a project, the customer is automatically lead to Esdec's project engineering department where special calculations are made in close collaboration with them.

The current state-of-the-art for solar structure design typically goes beyond the minimum code requirements to include an assessment of the unique pressure coefficients for the geometry of the structure. The pressure coefficients are typically obtained from wind tunnel testing performed on a scale model of the solar structure and an experienced wind tunnel laboratory. As is best practice, Esdec has obtained pressure coefficients from wind tunnel testing performed by Peutz in July and August 2020.

Peutz has conducted a boundary layer wind tunnel testing on a scale model of the Esdec FlatFix Wave mounting system following EN1991-1-4 Section 1.5, CUR C103 *Études en soufflerie des charges de vent sur les batiments (de grande hauteur)* and NEN 7250:2014 *Systèmes Énergie solaire – integration dans les toitures et façades – aspects dut bâtiment* (Figure 2-4). Peutz consulted TNO (Netherlands Organisation for Applied Scientific Research) on the obtained wind loads in order to increase the reliability of the results.

Results from Esdec's mechanical lift tests conducted in summer 2020 were incorporated into the wind tunnel data and then into the calculator of Esdec. Peutz has reviewed that these results have been correctly and safely processed in Esdec's calculations. Furthermore, the overall approach and method by Esdec have been tested and officially approved by Peutz in several reference projects (February 2022).



Figure 2-4 FlatFix Wave array/segment in the scale wind tunnel by Peutz (left) and uplift test by Esdec (right)

Wind tunnel results are presented in the form of pressure coefficients (C<sub>pe</sub> in accordance with EN1991-1-4). They are provided based on their position on the PV segment: courant (middle of the segment), bord (NS and EW perimeters away from the corners) and angles (at the corners) as a function of the normalized tributary area. Then, two verifications are performed: on every module and a group of modules. The second one is used to secure the ballast supported by the Dual Unit that provides system stability against sliding, lifting and overturning.



### 2.3.2 Snow Load

Similar to wind loading analysis, site-specific snow loads need to be calculated according to local standards. Given the low profile nature of the FlatFix Wave system, the system is not able to readily shed snow and it will collect snowfall and drifting snow with no "self-shedding" ability, thus snow represents a considerable design load for design.

Esdec has shown the racking structural calculation package to include the calculation of snow design loads according to applicable European standards.

### 2.3.3 Load Combinations

A method for combining the effects of wind, snow and dead loads is prescribed in building codes, Eurocode for Europe in particular. Often, the design of different racking components is governed by different load cases, e.g. wind loading may control the design for a module clip, whereas snow loading may govern the design of the supporting structure. DNV has confirmed that Esdec's load combinations are performed following European standard EN1990.

#### 2.3.4 Strength

To be structurally adequate for the conditions at a given location, the product must demonstrate the strength capability to withstand the calculated applied loads along with an additional margin of safety to account for areas of uncertainty. In Europe, regulatory requirements for structures such as the FlatFix Wave mounting system are typically established by the following codes:

Eurocode 1: Actions on structures; and Eurocode 3: Design of steel structures.

The typical controlling load scenario on PV racking structures is wind forces acting on the PV module glass and frames, but as noted previously all applicable loads need to be considered and combined according to appropriate standards. Each structural member in the complete load path should be analyzed for each of the load combinations. Esdec has performed it by previous physical testing which is deemed a suitable procedure according to DNV's viewpoint (see chapter 2.3.4.1).

#### 2.3.4.1 Mechanical Load Tests

Mechanical load testst (MLT) of the mounting system are performed to assess the allowable pressures or loads in the vertical direction, both positive (vertical down, simulating snow or wind downward loads), and negative (vertical up, simulating wind uplift). Tests were performed on the primary structure, on a two-module element using a FlatFix Wave full system and on single components (FlatFix Wave Dual Units). These mechanical tests also contribute to module clamp connections verifications (to High Base and Zipper).

Among others, the scope of the tests is the determination of characteristic values for the load-bearing of the components in order to apply for *allgemeine bauaufsichtliche Zulassung* (a "General Building Permit" in Germany).





Figure 2-5 FlatFix Wave MLT bending test

Esdec has also checked the friction coefficient to be used in the stability verification or ballast system design by subjecting the FlatFix Wave system to lifting and drag forces.

#### 2.3.5 Corrosion

According to Esdec documentation, FlatFix Wave main structural components are S250GD structural steel coated with Z310 (Magnelis coating). Z310 is comprised of Zinc, 3.5% Aluminum, and 3% Magnesium. FlatFix Wave brackets also have superior corrosion resistance, brackets are coated with Benzinal 2000 material.

To validate the corrosion resistance of FlatFix Wave components and brackets, VDE, entrusted by Esdec, has performed Sulphur dioxide test with general condensation of moisture in accordance with ISO 6988:1997-03 and Salt spray testing in accordance with EN 60068-2-52:2018-08. From the documents reviewed, FlatFix Wave parts are performing well and passed the certification process.

## 2.4 Electrical Engineering

### 2.4.1 Functional grounding, bonding and lightning protection

An important aspect of a mounting system is the equipment grounding system. National electrical codes usually require that accessible conductive components that are likely to become energized be adequately bonded to the ground.

Furthermore, standard HD-IEC 60364-7-712 requires that, where equipotential/ground bonding is necessary, the metallic structure supporting the PV modules including the metallic cable management systems shall be bonded. This bonding conductor shall be connected to any suitable earthing terminal and have a minimum cross section of 4 mm<sup>2</sup>. In addition, when metal structures are of aluminium, suitable connection devices shall be used to ensure a proper equipotential bonding.

In the case at hand, compliance with this requirement is easily fulfilled by ZM coated steel components clamped together as a robust structural assembly and electrically connected (i.e., a ground wire does not need to be run to each individual corrosion protected steel component). Nonetheless, PV frames are typically anodized aluminum and therefore have a non-conductive outer surface that must be penetrated to make a connection to a conductive material. Esdec's design addresses IEC requirements above through teeth surfaces without the need of additional means and components. Earth continuity



and integral bonding have been actually physically tested and certified by VDE in accordance with IEC 60364. Finally, a grounding connector ( $\geq$  4 mm<sup>2</sup> diameter) per PV field connects to at least one ground rail in an inverter (earthing terminal).




Figure 2-6 FlatFix Wave Teeth surfaces


With regards to lightning protection, FlatFix Wave system is tested, classified and approved according to EN 62305-1 Lightning Protection.

#### 2.4.2 Wire Management

Wire management is a very important aspect of solar PV systems and involves properly routing, supporting, and protecting PV system wires and cables. Wire management components typically do not have a standard warranty, and if not properly designed, it is likely to fail first, causing safety and reliability concerns. To ensure the longevity of solar PV systems, cables need to be properly secured and protected from direct sunlight, and other weather elements. In addition, they need to be protected from metal sharp edges, rodents, and other animals. It is particularly addressed by HD-IEC 60364 standards and fulfilled by Esdec by deploying the trays below the PV modules, over the ground and tied to predefined perforations and lips.

Esdec recommends using several components such as trays for securing wiring along modules and mounting system components. It is something deemed positive by DNV as being generally missing in the market.








Figure 2-7 FlatFix Wave wire trays

#### **3 RELIABILITY / DURABILITY EVALUATION**

While reliability is best evaluated from lifetime and field experience, analysis and laboratory testing can also inform the perspective on expected reliability.

Esdec has supplied rooftop solar mounting structures since 2004 for over 7 GW PV power capacity. The FlatFix Wave product has been installed in the field since 2020 with over 321 MW installed capacity. The design of this system provides a toolless installation procedure which increases the efficiency and reduces the labor cost. FlatFix Wave has not received any claims over 18 projects in 6 countries.

DNV notes that project owners, developers, and sponsors have increased project useful life expectations to 35 or even 40 years of life as of lately. DNV observed a continuous effort from Esdec to follow the market and adapt the product in case of a new practice.

#### 3.1 Test Programs and Certificates

Esdec acquires several certificates for the FlatFix Wave to assure the integrity and reliabity of the product. The certificates cover both general usability and detailed technical capabilities. Table 3-1 shows the test program for the FlatFix Wave product.

Besides these tests, Esdec planned several tests which are ongoing and provide higher reliability to the system.

Parameter	Description
Earthing and Lightning Protection	General requirement from HD-IEC 60364 series with focus on protective earthing, functional bonding and lightning protection.
Corrosion of the Earthing	Assessment of effective earth continuity under corrosion.

Table 3-1 FlatFix Wave Product Test Certificates



Plasticizer Migration	Determination of the effect of plastic solar feet on PVC roof sheeting.
Rooftop Fire Performance (Fire Listing)	These installations must meet a fire resistance index called BROOF (t3) which means that the time for the fire to penetrate through the roof and for the fire to spread to an exterior roof must be greater than 30 minutes.
Reaction to Fire Performance	Testing construction material to classify their reaction to fire based on EN 13501-1 standard.
Wind tunnel testing	Wind tunnel testing has been performed on the scaled model of the FlatFix Wave on a rooftop.
Experimental load test	Uplift and down pressure mechanical load tests were perfomed on the units to investigate the resistance and find out the coupling parameter.

FlatFix Wave has ENQUETE TECHNIQUE NOUVELL (ETN) and ALLGEMEINE BAUAUFSICHTLICHE ZULASSUNG (abZ) certificates which are building authority approval of useability for the construction product.

FlatFix Wave has the fire classification class of Broof (t3) according to CEN/TS 1187:2012 and EN 13501-5:2016 that is acceptable in France and other EU countries. FlatFix was tested based on EN 60068-2-52, EN ISO 6988 and EN 61439-1 for assessment of effective earth continuity.

FlatFix Wave uses corrosion protected steel from Arcelor Mittal with Magnelis coating. Esdec has performed the corrosion tests and the product warranty period is 20 years.

### 4 MANUFACTURING, OPERATION AND MAINTENANCE QUALITY EVALUATION

#### 4.1 Introduction

DNV reviewed FlatFix Wave's operation and maintenance documentation, installation procedures, and checklists. The manufacturing facilities have not been visited and the quality of the product is assessed based on quality control and supply management of Esdec as seen through the ISO 9001 Quality Management System certification.

Unlike other components of a solar facility such as PV modules and inverters that are fully assembled and tested in a factory environment, mounting systems are not completely "manufactured" until they are assembled and commissioned at a project site. The FlatFix Wave plan involves the shipment of components to the installation site, storage and staging onsite. The final assembly will be done by the contractors of the project on site. The design of the system is by Esdec and the production is done by selected, external and exclusively working for Esdec manufacturers. The manufactured components are transported and stored in Esdec's storage hall.

In this context, DNV views manufacturing of mounting systems to include not only fabrication of components but also the installation, assembly, and final commissioning of the racking as a system on site; only upon system completion the characteristics of product conformance are measurable, and the end-product ready for acceptance by the customer.



The scope of the manufacturing review for this report includes a review of the internal process controls that FlatFix Wave uses to qualify vendors, manages the supply chain, and controls the manufacturing functions at their facility. DNV's primary focus is on the quality management system and how FlatFix Wave assures the repeatability of its processes. DNV did not conduct an on-site evaluation of the suppliers' facilities.

DNV views the adequate management of each stage of racking production, installation, and commissioning as a priority for racking suppliers to deliver a quality final product to the end-user. Review and commentary on the production and maintenance policies of components for the racking are covered in this section.

#### 4.2 Site Visit

DNV visited Esdec main factory in Deventer, Netherlands in May 2022. The main factory includes the storage halls, logistic preparation, design offices, administration offices, Innovation center which included showroom and training center as well as and testlabs.

The storage and logistic halls were adequately signed for safety and operation and access areas were clearly marked (Figure 4-1). On the day of visit, some of the pallets were not in their designated location, which could be organised better.






Figure 4-1 the access and safety marks on site

The storage, offices and shared areas were organized and tidy. The electrical workshop and the showrooms were organized but the mechanical workshop needed a bit more organization as tools and materials were scattered. This is expected to be solved soon as Esdec had plan to improve the tests procedures.

#### 4.3 Supply Management

Esdec obtained ISO 9001-2015 conformity in 2022 from DNV Business Assurance. No non-conformities have been reported.

Esdec has reasonable sales and purchasing risk based strategy. In addition, they have a established system for vendor rating, suppliers audits and monitoring besides the internal auditing and PNC procedures (complaints and product deviations). The lessons learned from projects and also the data analysis on the PowerBI platform are part of Esdec's development. Although the firm has pitfalls in the logistics, there are many development actions on its list to improve the system. DNV finds the supply management adequate at the moment with improvement actions on the list.



#### 4.4 Manufacturing Procedure

DNV did not visit the manufacturing facilities, however, the ISO 9001 Quality Management System certificate has approved the supply chain management. In addition, as part of the ISO 9001 procedure, factory production control is done, based on which DNV expects the same level of manufacturing quality by Esdec.

#### 4.5 Installation

Similar to most solar PV mounting systems, Esdec delivers the FlaFix Wave system to the project site and provides instruction of the racking system, installation manual and inspection checklists (Section 2 explains the installation procedure thoroughly). The installation of the mounting structure is performed by contractors and installers and Esdec does not provide any aid or supervision on installation procedure, however, technical training is provided for the technicians who are doing that for the first time on-site or off-site at the Esdec factory. This technical training provides enough knowledge to prevent probable mistakes.

The installer holds the responsibility of performing the proper checks to verify the installed system is in conformance with the installation manual.

FlatFix Wave has adequate installation manual with an illustrative procedure for the installation of the mounting system (see Chapter 2). The FlatFix Wave checklist includes delivered material, alignment and placement, and installation procedure of the components. However, it does not provide any recommendation or awareness towards visual checks of corrosion protection coating and signs of physical damage to the racking components, and proper installation and checks for damage to the modules.

As noted earlier, Esdec provides support and training of installation on-site, however, the installer is responsible for verifying the installed system is in conformance with the installation manual, racking construction set, and O&M manual.

#### 4.6 Maintenance and Inspection

FlatFix Wave does not have a maintenance manual which explains the maintenance and inspection activities but Esdec has general maintenance and inspection checklists. FlatFix Wave maintenance and inspection checklists include:

- Initial Inspection during construction (before system commissioning)
- Comprehensive Inspection periodic inspection for possible maintenance
- Specific Inspection after any severe weather event

Initial Inspection outlines very comprehensive data collection from the installation quality, system configuration, rooftop installation, and ballast conditions. Esdec recommends their customers to use international recommended practice for solar modules inspections, so they do not recommend any time period.

Comprehensive inspection includes:

- Inspect roof condition: current condition versus the as-built documentation
- Inspect for damaged and/or displaced components
- Inspect the earthing/bonding condition.

DNV recommends Esdec to create a maintenance manual and include all recommendation for inspections.



DNV also notes several FlatFix Wave product features specifically designed with constructability and O&M, however, the project developer is responsible for the layout design of the rooftop systems.




Figure 4-2 FlatFix Wave walkway spacing

DNV has not reviewed any field data to opine on the robustness of the O&M procedures. However, DNV considers FlatFix Wave's general approach to be in-line with competing racking products, and the O&M manual comprehensive and well organized. DNV views design features included for O&M as industry-leading.

#### 4.7 Spare Parts

FlatFix Wave does not have a separate spare parts list, rather is a part of the product sheet. Any extra material or spares shipped would be a result of the sellable component quantities.

#### 4.8 Warranty


Esdec has clear terms and conditions on sales and delivery. The terms and conditions clarify the terms upon selling the product and also specifies the intellectual property rights. Moreover, the general terms covers all necessary clauses regarding the purchase, payment, return, liability, disputed and force majure. The product warranty warrants that the product will be free from defects in materials and workmanship for a period of 20 years from the date of shipment.

Overall the general terms and conditions and the warranty of FlatFix product appear to be standard and the longer term length than 20 years could be more favorable in the industry.

#### 5 BUSINESS EVALUATION

Esdec founded in 2004, develops, manufactures, and supplies solar rooftop mounting solutions for the residential, commercial, and industrial markets. The company is headquartered in Deventer, The Netherlands, and has more than 7 GW of installed capacity, mostly in Europe and US. Esdec entered the US market in September 2018, acquired EcoFasten in November 2018, and acquired IronRidge and Quick Mount PV in 2019. Further in 2020, expanded their business to India, acquired PanelClaw in USA and Solar Construct in The Netherlands. The latest acquisition of in 2021 includes Solarstell in The Netherlands.

Esdec Solar Group has regional headquarters in the United States, Europe and India that manage and support the various business units.



#### Figure 5-1 Esdec Business Units

As of 31<sup>st</sup> December 2020, a total of 266 (2019: 232) employees are working in Esdec Solar Group who represent full time equivalents. Of this, 83 (2019:59) are working in the Netherlands, 173 (2019:167) in the USA and 10 (2019:6) in the rest of Europe.




Figure 5-2 Esdec history and growth over the years

### 5.1 Financial Overview

The commercial overview is based on the annual report of 2020 and publicly available information, and comprise of Esdec Solar Group B.V. and subsidiaries. In 2020 Esdec Solar Group B.V. grew revenue by 60% year-on-year to a total of 244 Million EURO. The operational result was 34,4 Million EURO, improving from 11% in 2019 to 14% in 2020. The result after tax is reported as 8% in 2020, from 4% in 2019. The credit rating of Esdec Solar Group B.V. is reported as score A (Creditsafe, 11.05.2022).



#### Table 2: Summary of key financial figures( x1000 EUR)

Balance Sheet	31.12.2020	31.12.2019
Fixed Assets	€ 184 046	€ 181 622
Current Assets	€ 99 049	€ 87 503
Total Assets	€ 283 095	€ 269 125
Equity	€ 81 751	€ 68 066
Non-current Liabilities	€ 145 381	€ 148 758
Current Liabilities	€ 55 963	€ 52 301
Total Liabilities & Equity	€ 283 095	€ 269 125
Income Statement	31.12.2020	31.12.2019
Total Revenue	€ 243 999	€ 152 229
Total Cost	€ 209 635	€ 134 762
Operating Result	€ 34 364	€ 17 467
in percent of total revenue	14 %	11 %
Financial Income and Expenses	€ 7 557	€ 6 989
Result before Tax	€ 26 807	€ 10 478
in percent of total revenue	11 %	7 %
Income Taxes	€7316	€ 3 831
Result after Tax	€ 19 491	€ 6 647
in percent of total revenue	8 %	4 %
Cashflow Statement	31.12.2020	31.12.2019
Net cash generated from operating activities	€ 49 829	€ 18 932
Net cash generated from investment activities *	<b>-</b> € 33 108	-€ 87 635




Net cash generated from financing activities	<b>-</b> € 12 283	€ 77 612
Net cash flows	€ 4 438	€ 8 909

\*incl acquired cash from acquisitions

## 5.2 Product Roadmap and Vision

DNV was provided with the Research & Development plan for 2022 with a specific focus on the European market. The main vision for Research & Development is built around the core value of "increasing passion".





As diagramatically represented above, Esdec believes in focussing on the customer through gaining knowledge from the direct customers, markets and system. Further this knowledge is used to innovate and enhance focus by reducing time to market and prioritization, which helps in improved effectivity. Eventually, the organization team works towards standarization of the service/product to reach the final end result. This is eventually improved continuously by personal development, process and quality control. Esdec has a clear roadmap for new product development supported by their concrete sales strategy.

The Research & Development organization within Esdec consists of 5 departments which include Innovation, development of pitched roof, development of flat roof, research and structural Engineering and test and certification.



The entire team consists of 15-20 members as of June 2022, spread across the various departments with a strong ambition to increase the FTE further in 2022.

#### 5.3 Intellectual Property

The comprehensive work of the research and innovation department within Esdec gave rise to many novel products with a field of patents.

Esdec currently has 17 patents globally and have a few patents pending the final grant as of May 2021. The rights of these patents are protected by the European Union and US Patent Body. The patents have been granted to Esdec for innovation in the following :

- Assembly Process
- Mounting structure
- Support structure stability
- Clamping

### 6 CONCLUDING REMARKS

In its role as independent engineer, in addition to information gathered from Esdec representative, DNV has studied documentation provided by Esdec regarding the technical aspects of the FlatFix Wave mounting system, along with manufacturing and business systems. Based on available information, testing, and engineering that is indicated to have gone into the FlatFix Wave rooftop mounting products, DNV considers Esdec to be an organization which is well funded with strong financial health that, through qualitative design processes and extensive test procedures, is capable to supply suitable mounting systems that do not pose any atypical risks.



#### 7 REFERENCES

DNV has been provided with the following documentation for review by Esdec :

#### **Product Evaluation Documents**

- [1] 2138002 KIT Test Report.PDF
- [2] DNV Esdec FlatFix Wave module attachment.pdf
- [3] Esdec FlatFix Wave FMEA 05-22.pdf
- [4] Esdec FlatFix Wave Design review acc IEC60364.pdf
- [5] Esdec FlatFix Wave B ROOF t3.pdf
- [6] Esdec FlatFix Wave Fusion Roof Support.pdf
- [7] Esdec FlatFix Wave manual ballast\_EN\_124-1.pdf
- [8] Esdec FlatFix Wave manual\_EN\_129.pdf
- [9] Esdec FlatFix Wave Peutz 03-21 (confidential).pdf
- [10] Esdec FlatFix Wave Peutz approval 02-2022.pdf
- [11] Esdec FlatFix Wave Certification 03-2022.pdf
- [12] Esdec FlatFix Wave corrosion bonding 06-21.pdf
- [13] Esdec FlatFix Wave funct design calculator.pdf
- [14] Esdec FlatFix\_WavePlus brochure\_EN\_212.pdf
- [15] Esdec General Terms.pdf
- [16] Esdec Warranty 01-22.pdf
- [17] Eurocodes JW05.pdf
- [18] K21-6021 Expertise ESDEC FlatFix Wave\_mU.PDF
- [19] Koppeling Schuif Grote Velden.pdf
- [20] Project plan Newtonstraat example.pdf
- [21] Projectplan FlatFix Wave IKEA Portugal.pdf
- [22] Projectplan FlatFix Wave VDL Nedcar Born.pdf
- [23] Projectplan FlatFix Wave -Aldi Portugal.pdf
- [24] Projectplan\_Newtonstraat\_17\_\_\_anoniem\_Roof\_1.pdf
- [25] Testplan Wave lift- schuif 02-21.pdf
- [26] 201115\_HighBase\_R06.PDF
- [27] 201116\_HighBaseClamp\_R03.PDF
- [28] 201117\_Stabilizer\_R05.PDF



- [29] 201118\_BaseProfileL2300\_R03.PDF
- [30] 201119\_Coupler\_R04.PDF
- [31] 201120\_Zipper\_R04.PDF
- [32] 201121\_DeflectorA\_R02.PDF
- [33] 201122\_DeflectorB\_R02.PDF
- [34] 201123\_PerimeterCoupler\_R02.PDF
- [35] 201166\_BaseProfileL2460\_R01.PDF
- [36] 301066\_RoofSupport\_R05.PDF
- [37] 601062\_AssyShaslick\_R02.PDF
- [38] 601065\_ConnectorPinA\_R03.PDF
- [39] 601066\_ConnectorPinB\_R03.PDF
- [40] 601068\_BallastBracket\_R02.pdf
- [41] 701089\_HighBaseAssy\_R04.pdf
- [42] 701096\_Dual Unit 4P\_02.pdf
- [43] 701098\_Dual Unit 2P\_02.pdf
- [44] Esdec FlatFix Wave datasheet\_EN201.pdf
- [45] FlatFixWave\_SystemDimensionsOverview 10-20.pdf
- [46] 20200825 Decleration on ESDEC FlatFix Wave System.pdf
- [47] ETN Esdec FlatFix Wave no ETN L.21.06011av1.pdf
- [48] GCL Esdec FlatFix-Wave-Panel-Approval.pdf
- [49] JA Solar FlatFix-Wave-Panel-Approval.pdf
- [50] Jinko Statement For Esdec FlatFix Wave Ballasted Mounting System-2020-07-28.pdf
- [51] LG Solar Compatibility Letter for ESDEC FlatFix Wave.pdf
- [52] Longi Approval Letter For ESDEC FlatFix Wave Racking System.pdf
- [53] Longi Solar Esdec FlatFix-Wave-Panel-Approval.pdf
- [54] Statement of compatibility between Talesun modules and ESDEC FlatFix Wave Racking System.pdf
- [55] Talesun Esdec FlatFix-Wave-Panel-Approval.pdf
- [56] Esdec FlatFix Wave Certification 03-2022.pdf
- [57] Esdec Flatfix Wave\_ High Level TDD review 06-2021.pdf
- [58] Flowchart schademelding v2.pdf
- [59] TR21061 Maximum Lift Force Wave C2 at full system failureV5 (1).pdf



- [60] TR22071\_Determination of clamp-gap increasement for FlatFix Wave.pdf
- [61] TR22073\_coefficient of friction gravel fusion-wave.pdf
- [62] TR22080 Wave Module Locker strength validation.pdf
- [63] TR22082 Wave High Base Rail Lock strength validation.pdf
- [64] Close out meeting presentatie DNV 9001 RC mei2022.pdf
- [65] Esdec FlatFix Wave manual\_EN\_129.pdf
- [66] Esdec ISO9001 certificate EN.pdf
- [67] EsdecBV\_RC\_Management Summary Report\_2022-06-13T142931363Z.pdf
- [68] Esdec FlatFix Wave manual\_EN\_129.pdf
- [69] Esdec FlatFix Wave product sheet.pdf
- [70] Esdec-Inspectie-Certificaat-2.pdf
- [71] Esdec-Onderhoud-Certificaat-2.pdf
- [72] Esdec-Schouw-Certificaat-2.pdf
- [73] TD18\_Inspecties\_van\_zonnestroominstallaties-versie\_1.3-2021-10.pdf
- [74] Esdec Corporate PP presentation EN.pdf
- [75] Esdec FlatFix Wave referencelist 04-22.pdf
- [76] Esdec roadmap 2022 DNV abstract.pdf
- [77] Esdec Solar Group B.V. Annual report 2020 (KvK).pdf
- [78] Patentwerk Esdec 210527\_list.pdf
- [79] R&D programs abstract for DNV.pdf
- [80] Esdec\_Solar\_Group\_B.V.\_NL-X-709486820000\_2022-05-05\_13-44-18.pdf



#### IMPORTANT NOTICE AND DISCLAIMER

This document is intended for the sole use of the Customer as detailed on the front page of this document to whom the document is addressed and who has entered into a written agreement with the DNV entity issuing this document ("DNV"). To the extent permitted by law, neither DNV nor any group company (the "Group") assumes any responsibility whether in contract, tort including without limitation negligence, or otherwise howsoever, to third parties (being persons other than the Customer), and no company in the Group other than DNV shall be liable for any loss or damage whatsoever suffered by virtue of any act, omission, or default (whether arising by negligence or otherwise) by DNV, the Group, or any of its or their servants, subcontractors, or agents. This document must be read in its entirety and is subject to any assumptions and qualifications expressed therein as well as in any other relevant communications in connection with it. This document may contain detailed technical data which is intended for use only by persons possessing requisite expertise in its subject matter.

This document is protected by copyright and may only be reproduced and circulated in accordance with the Document Classification and associated conditions stipulated or referred to in this document and/or in DNV's written agreement with the Customer. A Document Classification permitting the Customer to redistribute this document shall not thereby imply that DNV has any liability to any recipient other than the Customer.

This document has been produced from information relating to dates and periods referred to in this document. This document does not imply that any information is not subject to change. Except and to the extent that checking or verification of information or data is expressly agreed within the written scope of its services, DNV shall not be responsible in any way in connection with erroneous information or data provided to it by the Customer or any third party, or for the effects of any such erroneous information or data whether or not contained or referred to in this document.

Any forecasts, estimates, or predictions made herein are as of the date of this document and are subject to change due to factors beyond the scope of work or beyond DNV's control or knowledge. Nothing in this document is a guarantee or assurance of any particular condition or energy output.



#### **About DNV**

We are the independent expert in assurance and risk management. Driven by our purpose, to safeguard life, property and the environment, we empower our customers and their stakeholders with facts and reliable insights so that critical decisions can be made with confidence. As a trusted voice for many of the world's most successful organizations, we use our knowledge to advance safety and performance, set industry benchmarks, and inspire and invent solutions to tackle global transformations.